KOLAR DIVISION.

Notification dated 18th May 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, Chikmagalur, up to 2 P.M. on 8th June 1940, for restoring and raising the capacity of Bachimakalapalli Doddakere Reg. No. 626, Mulbagal Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kolar Division, should be addressed to the Executive Engineer, Kolar Division; in a seled cover and superscribed as "Tender for Restoring Bachamakalapalli Doddakere". The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a Treasury chellan for earnest money of Rs. 220 paid to the credit of "17 (*a*) P. W. Deposits" against the account of the Executive Engineer, Kolar Division. The earnest money of the successful tenderer will be retained as security for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 8th June 1940 at Kolar. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay specifications. A reserve of 5 per cent will be with held in the work bills of the contractor and the same repaid after the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Kolar, on all working days, between 11 A.M. and 5 P.M.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same. When lumpsum provisions are shown in the schedule of quantities the contractor, will be paid at either his tendered rate for each item or the prevailing schedule of rates in the division at the discretion of the Executive Engineer.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page, noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractors profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions, or additions at the discretion of the Executive Engineer or his representative and may be due to any reasons whatsoever. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of February 1941, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 5 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive

Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P.W.D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

N.B.—Copies of tenders in the prescribed form are obtainable from the office of the Executive Engineer, Kolar Division Kolar, only on a payment of annas four per form.

Abstract estimate for restoring and raising the Capacity of Bachimakalhalli Doddakere Register No. 626, Mulbagal Taluk (unrestored minor tank).

No.	Items of work	Unit	Rate	Quantity	Rates to be tendered
	BUND R. L. 57·00.		Rs. a. p.		Rs.
1	Clearing jungle with roots	Grade	1 8 0	12	
2	Cutting grips and steps to receive new earth	,,	1 8 0	12	
3	Removing ant-hills and filling with sand ..	Each	0 8 0	22	
4	Earthwork to bund including watering and tamping	C.yd.	0 3 0	5,800	
5	Removing and resetting old stone work with new jelly wedging	,,	0 8 0	406	
6	New rough stone revetment	,,	1 8 0	1,097	
7	Turfing to slopes	S.yd.	0 0 9	4,472	
8	Gravelling the top of bund including lead and consolidation	C.yd.	0 6 0	103	
9	Providing and fixing new B.M. stones including figuring and painting	Each	2 8 0	2	
10	Do do Register No. stones	,,	3 0 0	1	
11	Do do Grade Stones ..	,,	1 8 0	13	
12	Do do Index Stones ..	,,	0 6 0	13	
	Total ..				
	SLUICE AT R. L. 44·00.				
1	Cutting open the bund and refilling with watering and tamping	C.yd.	0 5 0	112	
2	Earthwork excavating foundation	,,	0 2 6	4	
3	Burnt stone jelly concrete in surki mortar ..	C.ft.	0 4 0	83	
4	Burnt stone in surki mortar with bond stones	Sqr.	0 4 6	183	
5	Cement mortar pointing (1 : 3 proportion) after racking joints	Sqr.	3 8 0	2·00	

No.	Items of work	Unit	Rate	Quantity	Rates to be tendered
			Rs. a. p.		Rs.
6	Burnt stone slabs 6" thick, dressed and fixed in surki mortar ..	S.ft.	0 4 0	69	
7	Drilling holes for orifice ..	Each	1 0 0	4	
8	Providing and fixing C.I. pipes 6" dia. including carting charges ..	R.ft.	3 0 0	42	
9	Providing and fixing plug and rod with locking arrangements, etc. ..	Each	10 0 0	1	
10	Clearing approaches in front and rear ..	L.S.	..	..	
	Total ..				
	III. WASTE WEIR AT R. L. 52·00.				
1	Earthwork excavating foundation	C.yd.	0 2 6	36	
2	Burnt stone jelly concrete in surki mortar ..	C.ft.	0 4 0	228	
3	Burnt size stone in surki mortar with bond stones	,,	0 4 6	676	
4	Burnt stone slab 6" thick, dressed and fixed in surki mortar	S.ft.	0 4 0	268	
5	Cement mortar (1 : 3) pointing after racking joints	Sqr.	3 8 0	5·6	
6	Stone jelly filling below apron	C.yd.	0 12 0	115	
7	New rough stone work with jelly wedging ..	,,	1 8 0	149	
8	Joggle joints	Each	0 8 0	5	
	Total ..				

Notification dated 21st May 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 11th June 1940, for restoring Karehalli Nandikere Tank Reg. No. 363—726 in Kolar Taluk (unrestored minor tank.)

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kolar Division, should be addressed to the Executive Engineer, Kolar Division, in a sealed cover and superscribed as "Tender for Restoring Karehalli Nandikere Tank." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a treasury challan for earnest money of Rs. 140 paid to the treasury to the credit of "17(*a*) P. W. Deposits," against the account of the Executive Engineer, Kolar Division. The earnest money of the successful tenderer will be retained as security for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 11th June 1940 at Kolar. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental schedule contract form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay Specifications. A reserve of 5 per cent will be withheld in the work bills of the contractor and the same repaid after the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Kolar, on all working days between 11 A.M. and 5 P.M.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same. When lumpsum provisions are shown in the schedule of quantities the contractor will be paid at either his tendered rate for each item or the prevailing schedule of rates in the Division at the discretion of the Executive Engineer.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative and may be due to any reasons whatsoever. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of December 1940, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 5 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.

(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

N.B.—Copies of tenders in the prescribed form are obtainable from the Office of the Executive Engineer, Kolar Division, Kolar, only on a payment of four annas per form.

Abstract estimate for restoring Karehalli Nandikere, unrestored Minor Tank Register No. 363-726, Kolar Taluk.

No.	Items of work	Unit	Rate	Quantity	Rates to be tendered
	BUND AT R. L. 56·00		Rs. a. p.		
1	Jungle clearing with roots	Grade	1 8 0	20	
2	Cutting trenches and grips to receive new earth	,,	1 8 0	20	
3	Removing ant-hills and filling with sand	L.S.	..	..	
4	Earthwork to bund including watering and tamping	C.yd.	0 3 0	8,384	
5	Turfing the slopes	S.yd.	0 0 9	8,186	
6	Removing and resetting old revetment with new jelly wedging near sluice apron and wings of weir	C.yd.	0 8 0	225	
7	Providing and fixing new grade stones	Each	1 8 0	23	
8	Do do index stones	,,	0 6 0	23	
9	Painting and fixing B.M. stones	,,	1 0 0	2	
10	Providing and fixing Register No. Stone	,,	3 0 0	1	
	SLUICE AT R. L. 46·00.				
1	Earthwork cutting open the bund and refilling with watering and tamping	C.yd.	0 5 0	10	
2	Burnt stone jelly concrete in surki mortar	C.ft.	0 4 0	75	
3	Burnt size stones in Surki mortar with bond stones	,,	0 4 6	126	
4	Burnt stone slabs 6″ thick dressed and fixed in surki mortar	S.ft.	0 4 0	51	
5	Cement mortar pointing (1 : 3) after raking joints	Sqr.	3 8 0	1·88	
6	Providing 6″ dia. C.I. pipes including fixing, carting and railway freight, etc., complete.	R.ft.	3 0 0	36	
7	Providing and fixing plug and rod with locking arrangements	Each	10 0 0	1	
	WASTE WEIR AT R. L. 51·00.				
1	Earthwork excavating foundation	C.yd.	0 2 6	28	
2	Burnt stone jelly concrete in surki mortar	C.ft.	0 4 0	304	
3	Burnt size stone in surki mortar with rough stones	,,	0 4 6	669	
4	Burnt stone slabs 6″ thick dressed and fixed in surki mortar	S.ft.	0 4 0	122	
5	Cement mortar pointing (1 : 3) after racking joints	Sqr.	3 8 0	7·00	
6	Old rough stone work with jelly wedging (charged to Bund)	..	..	..	
7	Joggle joints 8′ from c to c	Each	0 8 0	7	
	Total				

Notification dated 21st May 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 10th June 1940, for restoring Begli Belchenahalli Tank [Reg. No. 647/783 in Kolar Taluk (unrestored minor tank).

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kolar Division, should be addressed to the Executive Engineer, Kolar Division, in a sealed cover and superscribed as "Tender for restoring Begli Belchenahalli Tank". The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a treasury chellan for earnest money of Rs. 135 paid to the treasury to the credit of "17 (*a*) P. W. Deposits" against the account of the Executive Engineer, Kolar Division. The earnest money of the successful tenderer will be retained as security for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 10th June 1940 at Kolar. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental schedule contract form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay specifications. A reserve of 5 per cent will be withheld in the work bills of the contractor and the same repaid after the due fulfilment of the contract.

6. Failure to comply with the condition 5 above, or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Kolar, on all working days between 11 A.M. and 5 P.M.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same. When lumpsum provisions are shown in the schedule of quantities, the contractor will be paid at either his tendered rate for each item or the prevailing schedule of rates in the Division at the discretion of the Executive Engineer.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof; or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer, on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative and may be due to any reasons whatsoever. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of November 1940, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 5 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over.

of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover, and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and must take precaution against all risk of accidents and if necessary provide for the same by Insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

N. B.—Copies of tenders in the prescribed form are obtainable from the office of the Executive Engineer, Kolar Division, Kolar, only on a payment of Re. 0-4-0 per form.

Abstract estimate for restoring and raising the capacity of Belachenhalli Dodkere (unrestored Minor Tank), Register No. 647—783, Kolar Taluk.

No.	Items of work	Unit	Rate	Quantity	Rates to be tendered
	BUND AT R. L. 56·50.		Rs. a. p.		Rs.
1	Clearing thickly grown jungle with roots ..	Grade	1 8 0	14	
2	Removing big ant-hills (8′×6′×4′) and filling the same with sand	,,	1 8 0	7	
3	Earthwork excavation, cutting grips and trenches for the seat of new earthwork ..	,,	2 0 0	14	
4	Earthwork to bund with lead, watering and consolidation, etc.	C.yd.	0 3 0	4,457	
5	New rough stone revetment with jelly wedging	,,	1 8 0	487	
6	Turfing to slopes of bund	S.yd.	0 9 0	4,639	
7	Fixing old grade stones with figuring and painting	Each	0 8 0	8	
8	Providing and fixing new grade stones with figuring and painting	,,	1 8 0	17	
9	Do Index stones	,,	0 6 0	25	
10	Do Register No. Stone do ..	,,	3 0 0	1	
11	Fixing old B.M. stone on concrete bed ..	,,	0 8 0	1	
12	Providing and fixing new B.M. stone ..	,,	2 8 0	1	
	WASTE WEIR AT R. L. 52·00.				
1	Removing and refixing old burnt stone slabs in surki mortar	S.ft.	0 2 0	191	
2	Burnt brick in surki mortar	C.ft.	0 4 0	413	
3	New burnt stone slabs 6″ thick dressed and fixed in surki mortar	S.ft.	0 4 6	4	
4	Stone jelly concrete ramp in surki mortar ..	C.ft.	0 4 0	518	
5	Cement mortar plastering after raking joints (1 : 3)	Sqr.	7 0 0	9·00	
6	New rough stone work with jelly wedging ..	C.yd.	1 8 0	9	
7	Stone jelly wedging to existing apron ..	L.S.	..	..	
	Total ..				

Notification dated 19th May 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 11th June 1940, for restoring Konda Thimmanahalli Thummakunte Tank Reg. No. 318 (unrestored minor) in Mulbagal Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kolar Division, should be addressed to the Executive Engineer, Kolar Division, in a sealed cover and superscribed as "Tender for restoring Konda Thimmanahalli Thummakunte Tank." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a treasury chellan for earnest money of Rs. 145, paid to the treasury to the credit of "17 (*a*) P. W. Deposits," against the account of the Executive Engineer, Kolar Division, Kolar. The earnest money of the successful tenderer will be retained as security for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 11th June 1940 at Kolar. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental schedule contract form for the due fulfilment of the contract and for the execution of all items of work in accordance with the Bombay Specifications. A reserve of 5 per cent will be withheld in the work bills of the contractor and the same repaid after the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings, may be seen at any time at the Executive Engineer's Office, Kolar, on all working days between 11 A.M. and 5 P.M.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same. When lumpsum provisions are shown in the schedule of quantities, the contractor will be paid at either his tendered rate for each item or the prevailing schedule of rates in the division at the discretion of the Executive Engineer.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer, on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative and may be due to any reason whatsoever. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of December 1940, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 5 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should

bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D. so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

N.B.—Copies of tender in the prescribed form are obtainable from the Office of the Executive Engineer, Kolar Division, Kolar, only on a payment of four annas per form.

Abstract estimate for restoring Konda Thimmanahalli Thumkunte Tank, Register No. 318 of Mulbagal Taluk.

No.	Items of work	Unit	Rate	Quantity	Rates to be tendered
	I. BUND AT R. L. 55·00.		Rs. a. p.		Rs.
1	Clearing jungle with roots	Grade	1 8 0	14	
2	Earthwork excavation cutting grips and trenches for the seat of new earthwork ..	,,	1 8 0	14	
3	Earthwork to bund with lead watering and consolidation, etc.	C.yd.	0 3 0	6,577	
4	Turfing the slopes of bund	S.yd.	0 0 9	3,948	
5	Constructing new stone revetment with jelly wedging	C.yd.	1 4 0	712	
6	Providing new grade stones with painting and fixing	No.	1 8 0	14	
7	Do Index stones	,,	0 4 0	14	
8	Do Register No. stone ..	,,	3 0 0	1	
9	Do B. M. stones	,,	2 8 0	2	
	II. SLUICE.				
1	Conducting repairs to the existing sluice ..	L.S.	..	..	
2	Providing new plug and rod with locking arrangements	,,			

No.	Items of work	Unit	Rate	Quantity	Rates to be tendered
			Rs. a. p.		Rs.
	CONSTRUCTING A NEW MASONRY WEIR 75 FT. LONG.				
1	Earthwork excavation foundation using the same to bund with watering and consolidation	C.yd.	0 3 0	140	
2	Burnt stone jelly concrete in surki mortar ..	C.ft.	0 4 0	190	
3	Burnt size stone in surki mortar with bond stones	,, ,,	0 4 0	190	
4	New burnt stone slabs 6" thick dressed and fixed in surki mortar	S.ft.	0 4 0	147	
5	Cement mortar pointing after racking joints (1 : 3)	Sqr.	3 8 0	1·50	
6	Constructing new rough stone work with jelly wedging	C.yd.	1 4 0	62	
	Total ..				

Notification dated 19th May 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 10th June 1940, for restoring Alangur Devarakere tank Reg. No. 32 Mulbagal Taluk (unrestored breached minor tank).

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kolar Division, should be addressed to the Executive Engineer, Kolar Division, in a sealed cover and superscribed as "Tender for restoring Alangur Devarakere tank." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a Treasury chellan for earnest money of Rs. 200 paid to the Treasury to credit of "17(a) P. W. deposits" against the account of the Executive Engineer, Kolar Division. The earnest money of the successful tenderer will be retained as security for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 10th June 1940 at Kolar. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form, for the due fulfilment of the contract and for the execution of all items of work in accordance with the Bombay specifications. A reserve of five per cent will be withheld in the work bills of the contractor and the same repaid after the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force, will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Kolar, on all working days between 11 A.M. and 5 P.M.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same. When lumpsum provisions are shown in the schedule of quantities the contractor will be paid at either his endorsed rate for each item or the prevailing schedule of rates in the division at the discretion of the Executive Engineer.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative and may be due to any reasons whatsoever. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of February 1941, failing which, the Executive Engineer may, at his discretion, levy a penalty of Rs. 5 per day, which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents, and if necessary, provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

N.B.—Copies of tenders in the prescribed form are obtainable from the office of the Executive Engineer, Kolar Division, Kolar, only on a payment of Re. 0-4-0 per form.

Abstract estimate for restoring Alangur Devarkere, Minor Tank, Register No. 38 of Mulbagal Taluk (unrestored Minor Tank).

No.	Items of work	Unit	Rate	Quantity	Rates to be tendered
	BUND AT R. L. 57·00.		Rs. a. p.		Rs.
1	Clearing jungle with roots	Grade	1 8 0	18	
2	Earthwork excavation, cutting grips and trenches for the seat of new earthwork ..	,,	1 8 0	18	
3	Earthwork to bund from borrow pits with lead watering and consolidation, etc., complete	C.yd.	0 3 0	8,634	
4	Consolidation, charges for earth excavated from waste weir and used for bund ..	,,	0 1 0	120	
5	Providing puddle wall in breached portion for strengthening the bund	,,	0 8 0	133	
6	New rough stone revetment with jelly wedging (Quarry in the work spot)	,,	1 4 0	1,063	
7	Turfing to slopes of bund	S.yd.	0 0 9	4,636	
8	Providing new grade stones with painting and fixing with bed slab	Each	1 8 0	19	
9	Providing and fixing Index stones ..	,,	0 4 0	19	
10	Do Register No. stone including painting and fixing	,,	3 0 0	1	
11	Do new B.M. stones do ..	,,	2 8 0	2	
	SLUICE BETWEEN C.S. NOS. 2 AND 3 WITH CILL AT 44·23.				
	Patch repairs to masonry works and providing new plug and rod with locking arrangement, complete	L.S.	..	..	
	CONSTRUCTING A MASONRY WASTE WEIR AT RIGHT SIDE OF THE TANK AT R.L. 52·00—90 FEET LONG.				
1	Earthwork excavation foundation	C.yd.	0 2 6	120	
2	Burnt stone jelly concrete in surki mortar ..	C.ft.	0 4 0	222	
3	Burnt size stone in surki mortar	,,	0 4 0	421	
4	Providing burnt stone slabs 6″ thick dressed and fixed in surki mortar including joggle joints	S.ft.	0 4 0	169	
5	Cement pointing after raking joints (1 : 3) ..	Sqr.	3 8 0	5·20	
6	New rough stone work with jelly wedging ..	C.yd.	1 4 0	47	
	Total ..				

Notification, dated 20th May 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 8th June 1940, for restoring Byrasandra Tank (unrestored minor Tank), Chintamani Taluk.

2. Tenders in the prescribed form obtainable form the Office of the Executive Engineer, Kolar Division, should be addressed to the Executive Engineer, Kolar Division, in a sealed cover and superscribed as "Tender for Restoring Byrasandra Tank." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a treasury chellan for earnest money of Rs. 325 paid to the treasury to the credit of "17 (a) P. W. Deposits," against the account of the Executive Engineer, Kolar Division. The earnest money of the successful tenderer will be retained as security for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 8th June 1940 at Kolar. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himsels to accept the lowest or any tender, or to aasign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay Specifications a reserve of 5 per cent will be withheld in the work bill of the contractor and the same repaid after the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force, will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Kolar, on all working days between 11 A.M. and 5 P.M.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same when lumpsum provisions are shown in the schedule of quantities the contractor will be paid at either his tendered rate for each item or the prevailing sehedule of rate in the division at the discretion of the Executive Engineer.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department Schedule of Rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative and may be due to any reasons whatsoever. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of July 1941, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 5 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed, and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(a) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.

(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.

(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

N.B.—Copies of tenders in the prescribed form are obtainable from the office of the Executive Engineer, Kolar Division, Kolar, only on a payment of Re. 0-4-0 per form,

Abstract estimate for restoring Byrasandra Tank, Register No. Nil, unrestored minor tank in Chintamani Taluk.

No.	Items of work	Unit	Rate	Quantity	Rates to be tendered
	I. BUND AT R.L. 58.50 TOP WIDTH 4½ FT.		Rs. a. p.		Rs.
1	Celaring jungle with root	Grade	2 0 0	13	
2	Cutting grips and trenches for seat of new earthwork	,,	2 0 0	13	
3	Removing anthills and refilling the hollow with sand	Each	0 8 0	10	
4	Earthwork excavation from barrow pits and using it for bund including watering and consolidation	C.yd.	0 3 0	4,120	
5	Removing and resetting old revetment with new jelly wedging	,,	0 8 0	385	
6	Constructing new stone revetment with new jelly wedging	,,	1 8 0	908	
7	Gravel backing to revetment	,,	0 6 0	302	
8	Providing and fixing new grade stone ..	Each	1 8 0	16	
9	Do do Index stones ..	,,	0 6 0	16	
10	Do do Register No stone. ..	,,	3 0 0	1	
11	Do do B.M. stones ..	,,	2 8 0	2	
12	Turfing to slopes	S.yd.	0 0 9	3,866	
	Total ..				
	II. BUND R.L. 58·50 WITH A TOP WIDTH OF 10 FT. (ALTERNATIVE PROPOSAL).				
1	Earthwork to bund including watering and consolidation	C.yd.	0 3 0	8,262	
2	Constructing new rough stone revetment with jelly wedging	C.yd.	1 8 0	1,025	
3	Gravel backing to revetment	,,	0 6 0	342	
4	Turfing to slopes	S.yd.	0 0 9	3,907	
	Total ..				

N.B.—The quantities noted against each item for alternative proposals are only gross quantities.

No.	Items of work	Unit	Rate	Quantity	Rates to be tendered
			Rs. a. p.		Rs.
	SLUICE AT R.L. 46·00.				
1	Earthwork excavation cutting open bund ...	C.yd.	0 2 6	130	
2	Do do for foundation ..	,,	0 2 6	6	
3	Concrete stone jelly in surki mortar ..	C.ft.	0 4 0	138	
4	Burnt brick in surki mortar	,,	0 4 0	322	
5	Burnt stone slab 6″ thick dressed and fixed ..	S.ft.	0 5 0	146	
6	Cutting holes in orifice slabs, etc.	Each	0 8 0	4	
7	Plastering with surki mortar	Sqr.	3 0 0	3·27	
8	Providing and fixing a new plug and rod with locking arrangements	Each	15 0 0	1	
9	Refilling the cut opened portion with earthwork including consolidation and watering.	C.yd.	0 2 6	130	
10	Providing and fixing C.I. pipe 6″ dia. and including carting and fixing, etc., complete	R.ft.	3 0 0	48	
11	Cut opening bund, dismantling the existing sluice and refilling the cut opened portion with earthwork and consolidation.	L.S.	..	..	
	Total ..				
	Constructing another sluice same as above ..				
	Total ..				
	WASTE WEIR AT R. L. 53.00.				
1	Benching rock for foundation	S.ft.	0 6 0	715	
2	Size stone in surki mortar with necessary bond stones	C.ft.	0 4 6	3,055	
3	Size stone in cement mortar (1 : 3) ..	,,	0 8 0	213	
4	Cement mortar pointing after racking joints	Sqr.	3 8 0	25.40	
5	Burnt stone slabs 6″ thick dressed and fixed ..	S.ft.	0 5 0	46	
6	Rough stone work new with jelly wedging ..	C.yd.	1 8 0	15	
	Total ..				

C. R. IYENGAR,
Executive Engineer.

MYSORE DIVISION.

Abstract Notification dated 10th May 1940.

The attention of the public is invited to the detailed notification, dated 5th May 1940, published on pages 1089-1091, Part VI of the *Mysore Gazette*, dated 16th May 1940, regarding tenders for constructing a High Level Causeway across the Gundlu River along Kabbahalli Road from 3/117 of Bangalore-Nilgiri Road, Gundlupet Taluk.

The last date for lodging of tender is 1st June 1940 up to 12 NOON.

S. RAMASWAMY,
Executive Engineer.